

Pre-welded reinforcing assembly contributes to efficiency of Quick Span

By George T. Biro, P.Eng.
StelCrete Industries Limited

Hanson Pipe & Products Canada, Inc. has introduced the precast Quick Span with a pre-welded reinforcement assembly. It was installed in Waterloo, Ontario immediately north of the University of Waterloo campus by E & E Seegmiller Limited, contracted in March 2004 to undertake the Regional Road 50 (Northfield Drive) widening. Included in the \$5.6 million contract was the Westmount Road extension from Northfield Drive to Bearinger Road. The four-lane extension passes through the southern extremity of the Laurel Creek Conservation Area and crosses Laurel Creek. The width of the travelled road and design elements required by the Grand River Conservation Authority made a three-sided precast concrete structure the best alternative for the crossing.

Reinforcement assemblies for the Laurel Creek Quick Span were fabricated on a specially designed jig at StelCrete's Fort Erie plant, so that all assemblies were consistent including 30M rebar spaced at 150 mm on centre around the exterior corner of the bridge sections. The leg sections were additionally reinforced with wire stirrups, specially fabricated on the MEP automatic stirrup machine at Ronco Steel, StelCrete's affiliated plant in Burlington, Ontario. Precast concrete units were designed in accordance with the Canadian Highway Bridge Design Code to support significant loads from trucks and approximately 1.4 metres of earth fill. The assemblies were shipped to the precaster, as required, to speed production and to help make best use of floor space and human resources at the plant.

StelCrete is fully certified by The Canadian Welding Bureau (CWB) to CSA Standard W186M, "Welding of Reinforcing Bars in Reinforced Concrete Construction," and to CSA Standard W47.1, "Fusion Welding of Steel Structures." The first standard governs rebar assembly products produced, and the second standard covers products that incorporate structural shapes, such as



Pre-welded reinforcing assembly for Quick Span mould.

cast-in hardware for concrete work. Domestic steel is used in the assemblies and is CSA-certified under standard G30.18, "Billet-Steel Bars for Concrete Reinforcement."

Design flows of Laurel Creek through all seasons, as well as wildlife passage is accommodated by the structure. It was designed with a light portal in the centre for placement in the road median, and a cobble bed to enhance the aquatic ecosystem of the stream. StelCrete delivered two special assemblies for the cast-in place portal as well as assemblies for the concrete barrier walls with rebar dowels pre-attached to the reinforcing cages. Hanson's casting method meant that expensive dowel bar couplers could be substituted with normal rebar projecting through the top of the precast deck. Assemblies were also provided for 8 wing wall units, 20 typical units, and two narrow units to meet the overall culvert length specified on this project.

The culvert was installed in less than two days once the footings were poured in place. Pre-welded reinforcement assemblies contributed to meeting both the production schedule of the precaster and the installation schedule of the contractor. Combining precast products with out-sourced reinforcement assemblies has proved the efficiency and economy of this form of production and business practice.